


NOTES:


- + Approximate total length of existing boardwalk is 2,100 feet.
- +Replacement boardwalk and observation decks are proposed to be in the same location. New width of boardwalk is to be min. 5'-0" clear width (see plan and cross section detail). Note boardwalk section to be 8'-0" wide.
- + Boardwalk elevation to be no greater than 30" above ground level at any one location. Boardwalk shall conform to general gradients of the land, but not to exceed 5%. Side slope of boardwalk shall be zero (0).
- + In effort to keep boardwalk structure at a low profile. Metal joist hangers (Simpson or equal) may be used as necessary to maintain specified boardwalk heights and gradients.
- + Concrete footings shall be place on undisturbed native soil. Some excavation may be necessary to provide a level surface. Where level native surfaces cannot be obtained, a compacted Class II aggregate base surface will be permitted.



TYPICAL BOARDWALK CROSS-SECTION

Laguna Pt.Boardwalk - MacKerricher S.P.

NOT TO SCALE



LAGUNA POINT
BOARDWALK REPLACEMENT



DRAWING NOT TO SCALE

LAGUNA POINT BOARDWALK ENTRY AREA

NOTES: CONCRETE PAVEMENT SHALL BE MIN. 4" THICK WITH #2 RE-BAR REINFORCEMENT AT 24" O.C. SLOPES AND GRADES AS INDICATED ON THE PLAN. COLOR (LIGHT BROWN / TAN) TO BE INTEGRATED INTO MIX. ANY FILL PLACED TO MEET FINISHED GRADE REQUIREMENTS SHALL BE COMPACTED CLASS II AGGREGATE BASE, NOT TO EXTEND NO MORE THAN 12" BEYOND EDGE OF CONCRETE.

NATIVE PLANTING AREAS SHALL BE BUILT UP WITH IMPORTED SOIL SUITABLE TO MAINTAIN VEGETATION GROWTH. SOIL LEVELS SHALL BE MEET FINISHED GRADE OF CONCRETE AND BLEND TO EXISTING GROUND LEVEL AT THE OUTER EDGES OF PLANTING AREAS. PLANT SPECIES USED FOR REVEGETAION SHALL BE DETERMINED AND ACQUIRED BY THE DISTRICT RESOURCE ECOLOGIST.

REVEGETATE AREAS WITH NATIVE PLANTS. WILL REQUIRE IMPORTING OF SOIL MIXTURE TO RAISE GRADE IN ORDER TO MATCH HEIGHTS OF PAVED ENTRY.

BICYCLE PARKING

6 FT. WIDE WOOD BOARDWALK

EXISTING TREES

6' TYP.

CUT CURB AND RAMP

EXISTING 40 CAR PARKING LOT


EXISTING AC DIKE CURB TO BE MAINTAINED UNLESS NOTED.

COLORLED CONCRETE SURFACE WITH ROUGH BROOM FINISH (SEE NOTES). LINEAR GRADIENTS NOT TO EXCEED 5% AND CROSS SLOPE NOT TO EXCEED 2% IN ANY DIRECTION.

STEPS AS NECESSARY

LOCATE TRASH AND RECYCLING RECEPTICLES

ACCESSIBLE PARKING STALLS (3)



SCALE: 1" = 20'

Mac Kerricher State Park

LAGUNA PT. BOARDWALK

1999-2001 Deferred Maintenance Program

CALIFORNIA DEPARTMENT OF PARKS & RECREATION
RUSSIAN RIVER ~ MENDOCINO DISTRICT

APPROVED

DATE

DATE
JAN 2002

DRAWN BY

GPS

CHECKED

GPS

DRAWING NO.

640-0122

SHEET

2

OF 2